



तेजपुर विश्वविद्यालय / TEZPUR UNIVERSITY  
(केंद्रीय विश्वविद्यालय / A Central University)  
कुल सचिव का कार्यालय / OFFICE OF THE REGISTRAR  
तेजपुर-784028 :: असम / TEZPUR-784028 :: ASSAM

## **CORRIGENDUM NOTICE**

**ET-NIQ-~~5627~~35-DT-~~20~~25-02-2020**

The technical Specifications (TechSheet) mentioned/uploaded alongwith the NIQ No. ET-NIQ-5627-DT-20-02-2020 (Tender Id- 2020\_TEZU\_546592\_1) is replaced with a **(Revised Technical Specification) TechSheet.**

Further, the item job mentioned in the NIQ "Modern Art of Museum" may be read as **"Museum of Modern Art"**

**The other contents of the NIQ remain unaltered.**

  
Joint Registrar  
Tezpur University

**Revised-Technical Specifications cum Compliance Report**  
**(To be submitted on Company's/Firm's Letterhead Signed and Sealed)**

Item	Specification	Complied (Yes/No)	Remarks if any,
<p style="text-align: center;"><b>Plywood Panelling – 9 Nos of wall area.</b></p>	<ol style="list-style-type: none"> <li>1. Plywood paneling work to be executed over the grill surface without disturbing the existing structure at maximum of 10 ft. height (approx.).</li> <li>2. The joints of the plywood should be properly secured from passage of exterior light beam and air flow.</li> <li>3. The backside of the panels visible through the grills needs to be designed synchronizing with the central theme of the museum.</li> <li>4. The surface should be properly treated with wall-care putty/primer.</li> <li>5. The ply panels therefore need to be painted in matte finish to create a neutral background.</li> <li>6. Ceiling painting of the entire display area needs to be done.</li> <li>7. Exterior areas of the museum must be designed with synchronizing to the central theme.</li> <li>8. Carpeting work needs to be done.</li> </ol>		
<p style="text-align: center;"><b>SS/MS Frame Work</b></p>	<ol style="list-style-type: none"> <li>1. A heavy MS structure of 20-inch top-height in box shape needs to be installed in the floor and it should be attached to the wall.</li> <li>2. The box must be covered on the top and side with plywood of required thickness.</li> <li>3. A toughened glass box (jointless in the front side) for each display segment will be installed on the edge of the box-shaped MS framework.</li> <li>4. The glass-box will be secured with SS (Stainless Steel) framework of required measures- at least 35 mm in the lining of the box.</li> <li>5. The MS / SS frame work structure needs to be hidden at optimum level.</li> </ol>		
<p style="text-align: center;"><b>Toughened Glass box</b></p>	<ol style="list-style-type: none"> <li>1. A superior quality box of at least 8 mm thickness toughened glass with clear visibility needs to be installed in each display segments.</li> <li>2. The boxes should be air-tight at possible optimum level to secure the display objects from dust and moisture.</li> <li>3. The toughen glass box shall be openable / removable for due maintenance of the paintings</li> </ol>		
<p style="text-align: center;"><b>Lightings</b></p>	<ol style="list-style-type: none"> <li>1. The display objects should be properly illuminated from the top and bottom of the glass box.</li> <li>2. The sources of the light must be hidden from the viewer's eyes.</li> </ol>		



	<ol style="list-style-type: none"> <li>3. The intensity of the lights must be healthy for the objects despite giving proper illumination.</li> <li>4. The placement of the lights should be easily accessible for due maintenance.</li> </ol>		
<b>Signage/Boards</b>	<ol style="list-style-type: none"> <li>1. The placement of the signages needs to be executed as prescribed by the expert team in due course of time.</li> <li>2. Back-lite letters of different sizes may be required.</li> <li>3. Signage in outdoor will be hanging or standalone and placed appropriately with prescribed design.</li> </ol>		
<b>Digital Display</b>	<ol style="list-style-type: none"> <li>1. A 32-inch digital monitor compatible with memory sticks and USB drive for displaying purpose needs to be installed inside.</li> </ol>		

*Handwritten signature and date: 24/10/2024*